Capsule Summary SM-547 Stephen and Mildred Jones House Leonardtown Private

early 1920s

Situated on a small knoll overlooking Fenwick Street and Town Run in Leonardtown, the Stephen and Mildred Jones house represents an excellent example of an early-twentieth century, Craftsman Style bungalow. Constructed in the early-1920s, this frame, one-and-a-half story, three bay dwelling exhibits several modern building forms and materials that exemplified the drastic changes to the appearance of domestic architecture in Leonardtown.

While the Jones house was probably not the direct result of a house catalog popular during the era, the building features several characteristics that link it to early-twentieth century innovations in building technology and form. The rusticated concrete block foundation, squat columns with battered sides, false rafter tails, shed roof projections, dual-pitched gable roof, pressed metal shingles, and gable dormer were all combined to create a distinctive building shape and form.

Stephen M. and Mildred F. Jones were a couple who preferred this new architectural composition. On March 3, 1920, the Jones' purchased the one acre tract from I. Stanley and Ida F. Johnson for \$500 and soon after erected the dwelling on the property. The Jones house was closely followed by the construction of the Johnson store and house (SM-556). Interestingly, the Johnsons and Jones were related by marriage to one another. Both the Jones and Johnson buildings, therefore, reflect the desire for relatives to live near one another--a common but important theme that is rapidly disappearing. It also demonstrates the wide diversity in building forms available to Leonardtown's residents during the early-twentieth century.

SM-547, Stephen and Mildred Jones House St. Mary's County Maryland Comprehensive State Historic Preservation Data

<u>Historic Context</u> Geographic Organization: Western Shore

Chronological/Developmental Period: Industrial Urban Dominance, 1870-1930

Historic Period Theme: Architecture

Resource Type Category:

Building

Historic Environment: Town

Historic Function and Use: Residence

Known Design Source: None

MARYLAND INVENTORY OF

Maryland Historical Trust HISTORIC PROPERTIES State Historic Sites Inventory Form

Survey No. SM-547 Magi No. DOE __yes __no

<u> 1. Nam</u>	e (indicate p	referred name)		
historic Steph	en M. and Mildred F. Jo	ones House		
and/or common				
2. Loca	ation			
street & number	48 East Fenwick Stree	et	_	not for publication
city, town Leon		vicinity of	congressional district 3	3
state Maryland		county	county St. Mary's	
3. Clas	sification			
Category district _X_ building(s) structure site object	Ownership public both Public Acquisition in process being considered not_applicable	Status _X_ occupied unoccupied work in progress Accessible _X_ yes: restricted yes: unrestricted no	Present Use agriculture commercial educational entertainment government industrial military	museum park x private residence religious scientific transportation other:
4. Own	er of Prope	erty (give names an	d mailing addresse	es of <u>all</u> owners)
name Danie	el W. and Patricia Much	10W		
street & number	PO Box 213		telephone n	o.:(301) 475–5862
city, town Leona	ardtown	state	and zip code _{Maryla}	and 20650
		al Description		
courthouse, regi	istry of deeds, etc. St. N	Mary's County Courthouse		liber MRB 102
street & number				folio 156
city, town Leon	nardtown		state	Maryland
6. Rep	resentation	in Existing	Historical Surv	eys
title				
date			federal sta	te county loca
ے ository for seج	urvey records			•
	a. roy roomas	•		
city, town			state	

7. Description			Survey No. SM-547		
Condition X excellent good fair	deteriorated ruins unexposed	Check one unalteredx altered	Check one X original site moved date of move		

Prepare both a summary paragraph and a general description of the resource and its various elements as it exists today.

Contributing Resource Count: 1

7. Description

The Jones House is located at 48 Fenwick Street near the central business district of Leonardtown, Maryland. The dwelling is approached via a dirt road that passes in front of two other two story frame houses. These buildings border the Jones house to the west while Fenwick Street forms the southern boundary. A wooded tract forms the east boundary and a pair of frame dwellings mark the northern limits of the property. The house sits approximately 50 feet from Fenwick Street as the lot gently slopes to the north. The wooded tract to the east marks the beginning of a steep hill that descends to the east.

Constructed c. 1919-1920, the Jones House is a one-and-a-half story, three-bay, frame. Craftsman-style bungalow with a concrete block foundation and a gable roof. While currently covered with vinyl siding, the building was originally covered with wood clapboard. The primary or south elevation of the dwelling features a full length porch supported by four squat columns with sloping or battered sides that rest on rusticated concrete block piers. Between these columns and piers (except between the central two columns) is a balustrade composed of square balusters topped by a railing. The porch shades three symmetrically placed bays that consist of a centrally located doorway (with a rectangular transom) flanked on both sides by three-part windows. These windows exhibit a central twelve-over-one, double-hung sash window flanked on each side by a slender six-over-one, double-hung sash window. This elevation also features a centrally placed gable dormer with a pair of sliding windows. At the lowest juncture of the dormer and roof, the roof changes to a flatter pitch. This also occurs on the north elevation as well. The roof, itself, is covered with pressed-tin shingles and is pierced by two, interior, brick chimney flues.

Other notable characteristics include a shed roof projection on the west gable-end of the dwelling. Similar projections were found on William and Agnes Mattingly House on Church Street (SM-542). The Jones House also features an open cornice with exposed rafter tails on the south and north elevations and decorative (false) beams/braces on the east and west gable ends.

8. Sign	nificance	Survey No. SM-547	Survey No. SM-547		
Period prehistoric 1400–1499 1500–1599 1600–1699 1700–1799 1800–1899 x 1900–	archeology-historic agriculture architecture art	community planning landscape architecture conservation law economics literature education military engineering music exploration/settlement philosophy industry politics/government	religion science sculpture social/ humanitarian theater transportation		
Specific date	8	Builder/Architect			
	licable Criteria: <u>x</u> A and/or licable Exception:	BCD ABCDEFG			

Prepare both a summary paragraph of significance and a general statement of history and support.

Level of Significance: __national __state _xlocal

Situated on a small knoll overlooking Fenwick Street and Town Run in Leonardtown, the Stephen and Mildred Jones house represents an excellent example of an early-twentieth century, Craftsman Style bungalow. Constructed in the early-1920s, this frame, one-and-a-half story, three bay dwelling exhibits several modern building forms and materials that exemplified the drastic changes to the appearance of domestic architecture in Leonardtown.

While the Jones house was probably not the direct result of a house catalog popular during the era, the building features several characteristics that link it to early-twentieth century innovations in building technology and form. The rusticated concrete block foundation, squat columns with battered sides, false rafter tails, shed roof projections, dual-pitched gable roof, pressed metal shingles, and gable dormer were all combined to create a distinctive building shape and form.

Stephen M. and Mildred F. Jones were a couple who preferred this new architectural composition. On March 3, 1920, the Jones' purchased the one acre tract from I. Stanley and Ida F. Johnson for \$500 and soon after erected the dwelling on the property. The Jones house was closely followed by the construction of the Johnson store and house (SM-556). Interestingly, the Johnsons and Jones were related by marriage to one another. Both the Jones and Johnson buildings, therefore, reflect the desire for relatives to live near one another—a common but important theme that is rapidly disappearing. It also demonstrates the wide diversity in building forms available to Leonardtown's residents during the early-twentieth century.

9. Major Bibliographical References

Survey No. SM-547

10. Geographic	al Data		
Acreage of nominated property		rences	Quadrangle scale 1:24 000
Zone Easting Nort	hing	B Zone	Easting Northing
C		D	
Verbal boundary description a Same as per deed reference.	nd justification		
List all states and counties for	properties over	rlapping state or	county boundaries
state	code	county	code
state	code	county	code
11. Form Prepa	red By		
name/title Kirk E. Ranzetta, Hi	storic Sites Sur	veyor	
organization St. Mary's County P	lanning and Zoni	ng	date January 6, 1997
street & number 328 Washington S	treet		telephone (301) 475–4662
city or town Leonardtown			state Maryland

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 supplement.

The survey and inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

return to:

Maryland Historical Trust

Shaw House 21 State Circle

Annapolis, Maryland 21401

(301) 269-2438

MARYLAND HISTORICAL TRUST
DHCP/DHCD
100 COMMUNITY PLACE
CROWNSVILLE, MD 21032-2023
-514-7690

SM-547, Stephen and Mildred Jones House

St. Mary's County

8.1 Significance

Chain-of-title (Please note that all records can be found in the Land Records Office, St. Mary's County Courthouse in Leonardtown, Maryland unless otherwise noted.)

Reference: Liber MRB 102, Folio 156 Grantee: Daniel W. and Patricia Muchow

Grantor: Adele J. Van Devanter and Mildred F. Jones

Date: July 31, 1981

Notes: Located at 48 East Fenwick Street in Leonardtown, the 1.08 acre property was purchased for \$157,000. The deed also describes the property as once called "Orchard" and located beside I. Stanley Johnson's store.

Reference: Liber EBA 19, Folio 34

Grantee: Stephen M. and Mildred F. Jones Grantor: I. Stanley and Ida F. Johnson

Date: March 3, 1920

Notes: Purchased for \$500, the property is called "Orchard." Soon after this transaction this

house was built.

Reference: Liber EBA 17, Folio 456 Grantee: I. Stanley and Ida F. Johnson

Grantor: Delia H. Maddox, Cora Maddox Cole and Robert H. Cole, her husband, and Mattie


Maddox Key--all heirs of Susan R. Maddox

Date: June 8, 1919

Notes: This deed notes that the property contains about 12 acres and was purchased for \$2,750.

Unfortunately, there is no bean clause to continue the chain-of-title.

SM-547, Stephen and Mildred Jones House St. Mary's County 8.2 Significance



1928 Sanborn Fire Insurance Company map of Leonardtown, Maryland showing the Stephen M. and Mildred F. Jones house. Note that Madison Street is now called Fenwick Street. Map courtesy of Becky Proffitt and the Sanborn Fire Insurance Company Archives.

SM-547. Stephen and Mildred Jones House St. Mary's County 8.3 Significance

The Sheridan



he Sheridan is a popular type of bungalow, planned to give the utmost livable space for its size, 28 by 38 feet. The upkeep cost is very small. All the materials are high grade. The porch extends across the entire front of the bungalow and may be screened or glazed and used as a most desirable room. This house can be built with the rooms reversed.

Details and features: Eight rooms and one bath. Full-width front porch supported by paired square columns; gabled dormer; glazed front door.

Years and catalog numbers: 1925 (3224); 1926 (P3224); 1928 (C3224); 1929 (P3224)

Price: \$2,095 to \$2,256

As a Craftsman-style bungalow, the Jones house exhibited many similar characteristics to dwellings that were often featured in catalogs. "The Sheridan" represents one such similar design found in Sears, Roebuk, & Company house catalogs from 1925-1929. Note the comparable use of the gable roof dormer, full-width front porch, gable-end shed roof projections, exposed roof brackets, and six-over-one, double-hung sash windows. Katherine Cole Stevenson and H. Ward Jandl, Houses By Mail, A Guide to Houses from Sears, Roebuk, & Company (Washignton, DC: The Preservation Press, 1986), p. 145.

